



## Qulliq Energy Corporation

Technical Interconnection Requirements for  
Commercial and Institutional Power Producers  
Nunavut

Technical Specification

### **CIPP Technical Interconnection Requirements**

March 1, 2021

**FINAL**



## Technical Interconnection Requirements

Quillix Energy Corporation (QEC), its officers, directors and employees, make no warranties or representations and take no responsibility of any kind with respect to the information contained in this document, including, without limitation, its quality, accuracy, completeness or fitness for purpose. QEC will not be liable for and accepts no responsibility for any losses, claims, expenses or damages, if any, suffered by a user or because of any decisions made or actions taken or not taken based on this document. Any conclusions a user may derive from the information in this document or any reliance by the user on the information it contains shall be at the user's sole risk. The use of or compliance with these requirements may not absolve an CIPP of liability to QEC for any damages that QEC may be entitled to at law.

QEC reserves the right to amend any of these documents at any time without prior notice or warning to users of the information contained herein.



1.	Purpose and limitations .....	1
1.1	Purpose .....	1
1.2	Document limitations .....	1
1.3	Interconnection limitations.....	2
1.4	Liability .....	3
2.	Terms, definitions, and abbreviations .....	3
2.1	Definitions.....	3
2.2	Abbreviations .....	6
3.	Definition of responsibilities .....	7
3.1	CIPP responsibilities .....	7
3.1.1	Design and construction .....	7
3.1.2	Maintenance and operation .....	8
3.1.3	Modification to installations .....	8
3.2	QEC responsibilities.....	9
3.2.1	General.....	9
3.2.2	Studies.....	9
3.2.3	Development .....	10
3.2.4	Maintenance and operation .....	10
4.	QEC system characteristics.....	10
4.1	General.....	10
4.2	System frequency .....	11
4.3	Power quality.....	11
4.4	Voltage unbalance .....	11
4.5	Fault levels .....	11
4.6	System grounding .....	12
4.7	Fault and line clearing .....	12
5.	Interconnection requirements .....	12
5.1	General.....	12
5.1.1	Safety .....	12

Page ii

Page iii




Table 1: Frequency range with triggering prohibited (as per IEEE 1547) .....	17
Table 3: Time limits for protection responses to abnormal voltages .....	24
Table 4: Generator trip frequency limits (as per IEEE 1547) .....	25
Table 5: Equipment accuracies for active and reactive energy measurements .....	29

Appendix A: Information Required from the Prospective CIPP

Appendix B: Information Provided by the Utility


Appendix C: Typical Interconnection Single-Line Diagrams

Appendix D: Application Guidelines

Appendix E: Operating Procedures

Appendix F: QEC Power Plant General Information

Appendix G: QEC Distribution Systems Voltages





The guidelines in this document are minimum requirements for the interconnection of a Renewable Generation Facility. The Prospective CIPP may also have to meet additional or modified requirements to address unique situations and to meet all local and national standards and codes. Any exemptions to this requirement shall require QEC's prior written approval.

It is the CIPP's responsibility to match the system voltage and characteristics at the POI depending on the community, as required for interconnection. The CIPP shall also provide at its own cost all the necessary switchgear, protection equipment, distribution line extension and accessories, as required for the interconnection.






Option 2 – CIPP connected through the existing POI used to power the commercial and institutional facility.

QEC, by reason of such review or lack of review, shall not be responsible for the strength, adequacy of design or capacity of equipment built pursuant to such specifications, nor shall QEC or any of its employees or agents be responsible for any injury to the public or workers resulting from the operation of the CIPP's Renewable Generation Facility. This guideline does not absolve the CIPP of the responsibility to maintain and protect its own equipment and QEC's equipment, as well as to ensure the safety of its own personnel, QEC's personnel and the general public.

(ii) the Act.



**“Person”** means an individual, body corporate, firm, partnership, joint venture, trust, legal representative or other legal entity.



**“Visible-Break Disconnect”** means a switch or circuit breaker by means of which the Renewable Generating Facility can be disconnected under full load entirely from the circuits supplied by the generating facility. All blades or moving contacts must be connected to the generator side, and the design of the disconnecting device must allow adequate visual inspection of all contacts in the open position.



## 2.2 Abbreviations

Abbreviation	Definition
AC	Alternating Current
AVR	Automatic Voltage Regulation
CEC	Canadian Electrical Code
CIPP	Commercial and Institutional Power Producer
CSA	Canadian Standards Association
DC	Direct Current
EGIA	Electricity and Gas Inspection Act
EMI	Electromagnetic Interference
GCA	Generation and Connection Agreement
GPR	Ground Potential Rise
IEEE	Institute of Electrical and Electronics Engineers
NEMA	National Electrical Manufacturers Association
OCR	Oil Circuit Recloser
PLC	Programmable Logic Controller
POI	Point of Interconnection
PPA	Power Purchase Agreement
PV	Photovoltaic
QEC	Qulliq Energy Corporation
RGF	Renewable Generation Facility
RGEO	Renewable Generation End-Open
RGIT	Renewable Generation Interconnection Transformer
SCADA	Supervisory Control and Data Acquisition
SLD	Single-Line Diagram
THD	Total Harmonic Distortion
TIR	Technical Interconnection Requirements
TOV	Temporary Over Voltage
VAR	Volt-Ampere Reactive



The following sections define the responsibility of each party involved in the interconnection of Renewable Generation Facility with QEC's Power Distribution System.

Safety is a paramount requirement in the generation, transmission and distribution of electricity. The CIPP shall be responsible to ensure the Renewable Generation Facility meets all applicable federal, territorial, and local safety codes related to construction, operation and maintenance, including the Canadian Electrical Code, *Electricity and Gas Inspection Act* as well as Nunavut's *Electrical Protection Act* and *Safety Act*, as the legislation may be amended or replaced from time to time.

With regard to the development of a Renewable Generation Facility, the Prospective CIPP is responsible for:

1. providing information to QEC as specified in Appendix A;
2. if required by QEC, completing load flow and system impact studies to successfully integrate the Renewable Generation Facility within a reasonable period at the expense of the CIPP;
3. designing, procuring and supplying, shipping, constructing, installing, commissioning, owning, operating and maintaining the Renewable Generation Facility and distribution line facilities up to the Point of Interconnection (POI), including the following in respect of the Renewable Generation Facility:
  - a. ensure all necessary designs and drawings are signed and stamped by a professional engineer licensed to practice engineering in the jurisdiction of Nunavut;
  - b. have equipment certified by an Accredited Certification Organization;
  - c. construct according to Good Building Practices Guidelines document from a Government Authority;
  - d. verify that the installation conforms to the current edition of Part I (CSA C22.1) of the CEC; and
  - e. produce proof of Nunavut Electrical Inspector certification of the Renewable Generation Facility.
4. paying the costs of system interconnection (and any other costs to be borne by the CIPP according to QEC), subject to and in accordance with the other agreements between the CIPP and QEC;
5. obtaining any permits, certificates, licences, orders, approvals and other authorizations from any Governmental Authority as may be required for the design, construction, ownership,



- a. ensure that the local inspection and enforcement authorities accept the installation, or that the installation falls under the jurisdiction of an accredited entity under Applicable Laws;
- b. obtain and comply with any conditions attached to all regulatory approvals, including, but not limited to, land use and environmental assessment approvals, as necessary, for the construction and operation of the Renewable Generation Facility;
- c. inspect and approve all installations by an Electrical Inspector with the Government of Nunavut Safety Services Division;
- d. before commissioning and commencing any Parallel Operation:
  - i. obtain any approvals required to be obtained from QEC under these Technical Interconnection Requirements and under the PPA and GCA; and
  - ii. comply with the prerequisites and other requirements set out in this Technical Interconnection Requirements document in respect of joint operational matters, including technical and real time operations.
- e. obtain any permits, certificates, licences, orders, approvals and other authorizations from any Governmental Authority required to connect to the Power Distribution System; and
- f. provide copies of any of the foregoing to QEC upon request.

obtaining written approval from QEC before making any modification to the Renewable Generation Facility; and

coordinating the timing of any testing requirements for the commissioning of the Renewable Generation Facility with QEC.

The CIPP shall present to QEC the planned maintenance procedures and a maintenance schedule for the interconnection protection equipment and keep records of such maintenance.

The CIPP is responsible for making changes to their facilities at their own cost, as required from time to time, stemming from modifications made to QEC's Power Distribution System. In addition, when advised by QEC, the CIPP shall make changes, requested by QEC, to their facilities for




If the changes require modifications to the protection and control information, the CIPP shall obtain approval from QEC for the proposed modifications. To ensure that commissioning tests are performed correctly, QEC may require witnessing the tests and receiving written certification of the results.

### 3.2.1 General

The CIPP shall work with QEC to mitigate any adverse effects it has on the QEC Power Distribution System and is responsible for any costs incurred as a result.

After receiving the application for interconnection, QEC shall, if available, provide the Prospective CIPP with the information specified in Appendix B, at the Prospective CIPP's cost.




In connection with the development of a Renewable Generation Facility, QEC is responsible for:

- Page 10





Page 11




QEC distribution facilities are normally operated as effectively grounded with the exception of Resolute Bay, which is resistance grounded. The required short-circuit current contribution from the Prospective CIPP shall be evaluated on a case by case basis according to QEC's Power Distribution System.

To maintain the reliability of the Power Distribution System, QEC utilizes automatic re-closing. The Prospective CIPP shall take this into consideration when designing generator protection schemes to ensure that its equipment is well protected. Following a fault, the CIPP may be reconnected when the Power Distribution System is stabilized.

This document shall be read in conjunction with the IEEE 1547 Standard for Interconnection and Interoperability of Distributed Energy Resources with Associated Electric Power Systems Interfaces.

The Renewable Generation Facility interconnection shall conform to this guideline and to the applicable sections of the codes and standards listed within this document. When the stated version of the following standards is superseded by an approved revision, this revision shall apply.






The Prospective CIPP shall provide an isolation device (disconnect switch) capable of electrically isolating the Renewable Generation Facility from QEC's Power Distribution System.

In case of a low voltage disconnect switch, the disconnect switch on the generation side of the interconnection transformer shall be installed, owned and maintained by the CIPP.

1. be adequately rated to break the connected generation and load;
2. be manual and visible break and provide safe isolation for QEC's personnel from the Renewable Generation Facility and all other possible customer sources of energy;
3. be located as close as physically possible to the POI for high voltage interconnection, unless otherwise approved by QEC;
4. shall not use SF6 gas;
5. be gang operated to simultaneously isolate all three phases when the interconnection involves three-phase generators;
6. provide a direct, visible means to verify contact operation;
7. allow simultaneous disconnection of all ungrounded conductors of the circuit;
8. plainly indicate whether the switch is in the "open" or "closed" position;
9. be lockable, in the "open" position, and a visible break type. Keyed interlocks are not permitted;
10. be capable of energization from both sides;
11. be readily accessible to QEC operating personnel and not located in a locked facility or in a hazardous location;
12. be externally operable without exposing the operator to contact with live parts;
13. be capable of closing without risk to the operator when there is a fault on the system;
14. be capable of opening at rated load;
15. bear a warning to the effect that inside parts can be energized from sources on both sides when the disconnect switch is open;
16. be labelled with QEC's switch number; and
17. undergo annual inspections and maintenance.

Page 14



Grounding configurations of the CIPP shall be designed in accordance with QEC's system grounding to provide suitable fault detection in order to isolate all sources of fault contribution, including the generator, from a faulted line or distribution facility.

Lightning surge transferred and ground potential rise: The CIPP shall ensure that the installation does not increase the lightning surge transfer to QEC's system if the Renewable Generation Facility installation involves wind power generation or/and solar panels. To limit the exposure to lightning for QEC's Power Distribution System, lightning protection grounding shall be electrically separated from the grounding grid of the wind tower and/or solar panels. If the separation is not possible or practical, then the ground grids of the towers and/or solar panels shall be electrically separated from the Renewable Generation Facility ground grid to minimize the transferred lightning surges. The latter can be achieved by ensuring that the wind towers and/or solar panels are not bonded to the station ground grid.

### 5.2.4 Phasing

Conductor phasing is not standardized across QEC's Power Distribution Systems. The Prospective CIPP shall coordinate with QEC the phase sequence and direction of rotation during the design phase. The Prospective CIPP shall also connect the rotating machines as required to match the phase sequence and direction of rotation of QEC's Power Distribution System.

An interrupting device (e.g. circuit breaker) is required to automatically disconnect the Renewable Generation Facility from all ungrounded Power Distribution System conductors that the CIPP source feeds.

Page 15



It will be the Prospective CIPP's responsibility to conduct the necessary research, gather required data, conduct required system studies, and perform the interconnection study. The Prospective CIPP shall use all appropriate software to design the systems and provide for all requirements, including the current limiting and power flow control reactors, if required.

### 5.3.1 General system stability and integrity requirements

When a generation source is suddenly disconnected from the Power Distribution System, the result could be high-speed load shedding to maintain system stability and consequently, result in outage time to the Renewable Generation Facility. The Prospective CIPP is required to take note of this for their system design and is expected to have the required systems in place, such as an energy storage system and a controller for larger Renewable Generation Facility, in order to ensure system stability and adequate spinning reserve.

QEC's Power Distribution System is designed to operate for unidirectional power flow to the customers and voltage-regulating devices are designed to correctly operate under these conditions. However, with the addition of Renewable Generation Facility into the system, the power flow can be reversed when these facilities are supplying power, which may inhibit the voltage regulators ability to properly regulate the voltage on the feeder. If there is a possibility of reverse power flow, regulating devices (line voltage regulators, regulating stations and transformers under load tap changers at the POI on QEC's Power Distribution System) may need to be either upgraded or replaced with suitable devices that allow bi-directional flow. All costs related to required upgrades shall be borne by the CIPP.



### 5.3.2 Voltage stability

POI voltage shall be maintained within 0.95~1.05 p.u. and shall not be lower than pre-connection voltage. If high-voltage, low-voltage or voltage flicker complaints arise from other customers due to the operation of the Renewable Generation Facility, QEC reserves the right to isolate the Renewable Generation Facility from QEC's Power Distribution System until the problem has been resolved at the CIPP's cost, without compensation by QEC.

### 5.3.3 Frequency stability

The generators at the Renewable Generation Facility shall operate at a nominal frequency of 60 Hz and shall remain synchronously connected over the frequency range presented below.

Table 1: Frequency range with triggering prohibited (as per IEEE 1547)

Frequency range (Hz)
$59.8 \leq f \leq 60.5$

The generators shall trip in the time required, in accordance with IEEE 1547 requirements for any frequencies outside the frequency range presented in Table 1.

### 5.3.4 Synchronization

Any Renewable Generation Facility that can create AC voltage while separate from the Power Distribution System shall have synchronization facilities to allow its connection to the Power Distribution System.

Inverter-type, voltage-following equipment that cannot generate AC voltage while separate from the Power Distribution System does not require synchronization facilities; nor do induction generators that act as motors during start-up, drawing power from the Power Distribution System before generating their own power.







The Renewable Generation Facility shall not inject harmonic current that causes unacceptable voltage distortion on QEC's Power Distribution System. The Renewable Generation Facility shall follow the requirements of CAN/CSA C61000-3-6. The CIPP and/or QEC may be required to implement measures that will mitigate the harmonic distortions caused by the Renewable Generation Facility.

The CIPP shall not cause excessive voltage flicker on the Power Distribution System. The Renewable Generation Facility shall follow the requirements of CAN/CSA-IEC C61000-3-7. Any exception to the limits specified in the standard shall be approved by QEC.

The CIPP shall take flicker measurements using a device that conforms to CAN/CSA-C61000-4-15 or applicable standards, as may be amended from time to time. QEC may request this measurement if flicker complaints are received in the surrounding area.

The Prospective CIPP shall consider resonance in the design of the Renewable Generation Facility, as some resonance can cause damage to existing electrical equipment, including the electrical equipment of the CIPP. Engineering analysis by the Prospective CIPP shall be a part of the design process to evaluate the existence and elimination of the harmful effects of:

1. ferroresonance in the transformer; and
2. resonance with another customer's equipment.

In the event that an induction generator is used by the CIPP, the adverse effects of self-excitation of the induction generator during islanding conditions shall be assessed and mitigated. The intent is to detect and eliminate any self-excited condition.

The engineering analysis of resonance and the assessment of the self-excitation effects of induction generators shall be submitted to QEC for approval or further evaluation.

(only applicable for direct integration on QEC's Power Distribution System)

The Renewable Generation Interconnection Transformer (RGIT) shall not cause voltage disturbances or disrupt coordination of the Power Distribution System ground fault protection.

The CIPP shall ensure that there is no back feed from the RGIT when the generator is out of service and shall be responsible for all consequences resulting from such back feeds. The CIPP shall be responsible for ensuring that the design is adequate to handle the unbalance current.



#### 5.4.7 Batteries / DC supply

Batteries shall be provided with the Renewable Generation Facility and shall have adequate capacity to ensure that all protection functions operate when the main source of power fails. They shall remain operational for the time required for protection functions to operate properly and disconnect the Renewable Generation Facility from QEC's Power Distribution System. They shall also be capable of sustaining continuous telemetry about the Renewable Generation Facility connection status and Renewable Generation End-Open (RGEO) signals.

Batteries and chargers shall be connected to the main service supply or by using an uninterruptable power supply with sufficient capacity for the application. The battery voltage shall be monitored and upon failure, the protection scheme shall include an alarm. However, for network reliability concerns, QEC may require tripping the Renewable Generation Facility's generation source and disconnecting it from QEC's Power Distribution System.

Dual station batteries shall not be required for protection and control equipment. Protection systems designed to back each other up, shall be supplied by physically separated and protected (i.e. fused) DC circuits. Circuit breakers and the Renewable Generation Facility's interrupting device shall be powered by separate and dedicated DC circuits. Separate and independent means are to be used for tripping the Renewable Generation Facility's interrupting device and the Renewable Generation Facility's isolation device upon low voltage (DC) conditions.

Capacitors shall not be used as the primary means to store energy in lieu of batteries.


For a small Renewable Generation Facility, other methods or systems may be accepted by QEC if it is demonstrated that upon failure to power the relays, that alarm and trip function remain available, if required.

#### 5.4.8 Telecommunication requirements

(May be applicable for large Renewable Distribution Generation, as deemed necessary by QEC)

A telecommunication infrastructure is required for the Renewable Generation Facility connected to QEC's Power Distribution System to provide protection and real-time operating data. The telecommunication infrastructure shall be real time, secure, reliable, and meet the technical requirements for protection, control and monitoring. QEC may indicate the viable alternative technologies that may be used for telecommunications, which may include licensed/unlicensed microwave radio, optical fibre or carrier-based leased circuits.

The Renewable Generation Facility shall have a communication infrastructure compatible with QEC's SCADA system and include provision for remote trip.



Specified in this section are the typical interconnection requirements to safely operate the Renewable Generation Facility in parallel with the Power Distribution System.

For larger Renewable Generation Facilities, protection relays shall be “utility grade” and shall meet the requirements specified in the latest edition of IEEE C37.90, “Standard for Relays and Relay Systems Associated with Electrical Power Apparatus.” “Industrial grade” relays are not permitted for the interconnection protection unless deemed acceptable by QEC.

It should be noted that there may be specific interconnection locations and conditions that require more restrictive protective settings or hardware. QEC shall make these deviations known to the Prospective CIPP as soon as possible. The Prospective CIPP shall work closely with QEC to determine whether interconnection and operation within a specific network system is possible.

The maximum generated power of the Renewable Generation Facility shall respect the QEC system limitations, which will be defined in the interconnection study.

In certain cases, the maximum power of the Renewable Generation Facility could be limited in the case, for example, where the total Renewable Generation connected to a distribution feeder is significant or where the voltage unbalance is already significant (in the case of single-phase generation)

Page 21



The Prospective CIPP shall provide QEC with the complete documentation of the proposed interconnection protection scheme for review against the requirements of the Technical Interconnection Requirements, and for potential impacts to QEC's system.

1. an overall description of how the protection will operate;
2. a detailed single-line diagram of the Prospective CIPP facility up to the POI;
3. the identification details of the protection components (i.e., manufacturer, model, etc.);
4. the protection component settings (i.e., trigger levels and time values); and
5. the identification details of the disconnect switch (i.e. manufacturer, model and associated certification).

Relays with self-diagnostic features provide information on the integrity of the protection scheme and should be used whenever possible.

Where relays with the self-diagnostic feature do not trip the appropriate breaker(s), sufficient redundant or backup protection shall be provided for the Power Distribution System. The malfunctioning relay shall also send a signal to notify operating personnel to investigate the malfunction.

The CIPP's generator circuit breakers shall be three-phase devices with electronic or electromechanical control.

The CIPP shall also be responsible for ensuring that the interconnection protection device settings coordinate with QEC's own protective device settings.





- ## 6.6 Over-voltage and under-voltage protection

The protection of the interconnection facility shall cause the Renewable Generation Facility to cease energizing QEC's system within the trip times indicated in Table 2. The trip times listed in this table are the time periods between the start of the abnormal condition and the moment the interconnection device ceases to energize QEC's system. It should be noted that these values are subject to change based on the actual system variables at the time of installation.

**Table 2: Time limits for protection responses to abnormal voltages**

RMS voltage	Trip time(s)
V < 50%	6 cycles (0.1 s)
50% < V < 88%	120 cycles (2 s)
110%<V<120%	20 s
120% < V < 137%	120 cycles (2 s)
V > 137%	2 cycles (0.033 s)

## 6.7 Over-frequency and under-frequency protection

Page 24



Table 3: Generator trip frequency limits (as per IEEE 1547)


Frequency range (Hz)	
Low range	High range
< 59.8	> 60.5

An overcurrent protection device is required to automatically disconnect the CIPP from QEC's Power Distribution System for faults on the Renewable Generation Facility or the connection up to the POI.

1. account for present and future anticipated fault levels.
2. coordinate with the timed elements of upstream protective devices and be sensitive enough to operate at minimum QEC infeed faults.
3. locate the overcurrent protection device as close to the POI as is practical. It can either be on the first or second pole after the POI.
4. locate fault indicators visible from the POI with directional functionality for each phase between the POI and the first pole on the CIPP's new line.

## 6.9 Automatic re-closing

Page 25



It is an essential requirement that the Renewable Generation Facility have a built-in anti-islanding functionality compatible with the IEEE-1547-2018 standard. The anti-islanding functionality shall not have the ability to be re-programmed or disabled.

In most cases, the Renewable Generation Facility shall routinely operate as part of the interconnected system. A problem on the system could lead to the generator becoming islanded (i.e. the generator becomes the sole supplier of power to one or more of QEC's customers). The resulting irregularities in power quality could cause damage for other customers.

Where there could be a reasonable match between the CIPP's generation and the islanded load, conventional methods may not be effective in detecting the islanded operation. In this case, QEC will require the addition of transfer trip communication facilities to remotely trip off the CIPP's generation source upon opening the distribution feeder main circuit breaker or circuit re-closer.

The act of paralleling the CIPP Generator to the Power Distribution System can cause voltage fluctuation on the Power Distribution System, which should be restricted to a value of  $\pm 3\%$ .

1. Frequency difference less than + 0.5 Hz;
2. Voltage magnitude difference less than +2%; and
3. Phase angle difference less than a 5-degree lag.





Where a source of generation could adversely affect the Power Distribution System (e.g. by providing inflow into a fault), the CIPP shall have systems in place to inform QEC of the protective operations that occurred or failed to occur.


Where required, the transfer trip protection shall ensure that the Renewable Generation Facility does not experience islanding in the event of substation breaker or intermediate re-closer operation. The generator lockout shall be within 0.6 seconds of the breaker or re-closer operation.


Additionally, the Prospective CIPP needs to be aware that unbalanced conditions can occur in the Power Distribution System, especially under system fault conditions. This situation shall be taken into account in the design of the interconnection facility.

The CIPP's generator shall not energize QEC's facilities when these are de-energized.

The Renewable Generation Facility interconnection shall have the capability to withstand EMI environments in accordance with:

- Page 27





The metering equipment shall be:

1. compliant with applicable Measurement Canada requirements;
2. suitable for use in the environmental conditions that are reasonably expected to occur at the installation site over the course of a typical year; and
3. appropriate for the power system characteristics that are reasonably expected to exist at the installation site under all power system conditions and events.

An interval meter shall be installed by QEC at all Renewable Generation Facility sites at the expense of the CIPP and shall:

1. meet Measurement Canada requirements for revenue metering devices and be Measurement Canada-approved under Section 9(1), Section 9(2) or Section 9(3) of the *EGIA*;
2. be verified and sealed in accordance with the *EGIA*, and be subject to the terms and conditions of any applicable dispensation(s);
3. be capable of maintaining the interval boundaries within 60 seconds of the hour and every quarter hour thereafter;
4. measure all quantities required to determine active energy and reactive energy transferred in the required directions at the Measured Billing Point;
5. provide a separate register to maintain the continuously cumulative readings of the active energy and reactive energy transferred in the required directions at the Measured Billing Point;
6. retain readings and, if applicable, all clock functions for at least 14 days in the absence of line power; and
7. have an accuracy class rating for active and reactive energy measurements that equals or exceeds the values specified in Table 4:

Table 4: Equipment accuracies for active and reactive energy measurements

WATThour meter accuracy class	VARhour meter accuracy class
0.5%	1.0%

The applicable winding(s) of the current and potential instrument transformers shall:



- Page 30



Type testing is performed or witnessed once by an independent testing laboratory for a specific protection package. Once a package meets the type testing criteria described in this section, the design is accepted by QEC. If any changes are made to the hardware, software, firmware or verification test procedures, the manufacturer shall notify the independent testing laboratory to determine which, if any, parts of the type testing must be repeated. Failure of the manufacturer to notify the independent testing laboratory of any changes may result in the withdrawal of approval and disconnection of the units installed after the change has been made.

These testing procedures apply only to devices and packages associated with protection of the interconnection between the Renewable Generation Facility and QEC's system. Interconnection protection is usually limited to voltage relays, frequency relays, synchronizing relays, reverse current, or power relays and anti-islanding schemes. Testing of relays or devices associated specifically with protection or control of the Renewable Generation Facility is recommended, but not required unless the devices impact the interconnection protection.

At the time of production, all interconnecting equipment and discrete relays shall meet or exceed the requirements of ANSI /IEEE C62.41-1991 Recommended Practices on Surge Voltages in Low Voltage AC Power Circuits or C37.90.1 1989 IEEE Standard Surge Withstand Capability (SWC) Tests for Protective Relays and Relay Systems. If C62.41-1991 is used, the surge types and parameters shall be applied to the intended insulation location of the equipment, as applicable.

All interconnection equipment shall include verification testing of the transformer (voltage and turn ratio) as part of the documentation. There shall also be P&C commission testing to determine if the protection settings are adequate and meet the intent of the Technical Interconnection Requirements.

Page 31



## 8.4 Verification testing

Any system that depends on a battery for trip power shall be checked for proper voltage and logged monthly. Once every four years, the battery shall either be replaced or a discharge test performed.

## 8.5 Protective function testing

A reverse power or minimum power function, if used to meet the interconnection requirements, shall be tested using secondary injection techniques. Alternatively, this function can be tested by means of a local load trip test or by adjusting the CIPP output and local loads to verify that the applicable non-export criterion (i.e. reverse power or minimum power) is met.



If protective function settings have been adjusted as part of the commissioning process, the CIPP shall confirm that all devices are set to QEC's approved settings.

For protective devices with built-in metering functions that report current and voltage magnitudes and phase angles, or magnitudes of current, voltage, and real and reactive power, the metered values can be compared to the expected values. Alternatively, calibrated portable ammeters, voltmeters and phase-angle meters may be used.

Retesting of the potentially affected function shall be done whenever changes are made to interconnection hardware or software that may affect any one of the functions listed below:

- The above list of potentially affected functions is not exhaustive. QEC may request testing any other function it deems necessary.

QEC reserves the right to witness testing of installed switchgear and metering. The CIPP shall notify QEC at least 15 days in advance of any testing.



ᑭᓄᓴᓴᓴ ᑲᓴᓴᓴᓴᓴᓴᓴᓴ ᓴᓴᓴᓴ  
Quilliq Energy Corporation  
Société d'énergie Quilliq  
Quilliq Aᓴᓴᓴᓴᓴᓴᓴᓴ ᓴᓴᓴᓴᓴᓴᓴᓴ


## Technical Interconnection Requirements and Guidelines for Commercial and Institutional Power Producers

Technical Specification

**Technical Interconnection Requirements**

---

# Appendix A: Information Required from the Prospective CIPP







## Technical Interconnection Requirements for Commercial and Institutional Power Producers

Technical Questionnaire

Information required from CIPP – Proposal Stage

INFORMATION REQUIRED FROM IPP		
	REQUIRED AT PROPOSAL STAGE	REQUIRED AT DETAIL DESIGN STAGE
<b>1. Commercial and Institutional Power Producer Contact Information</b>		
1.1. Company Name	X	
1.2. Company Address	X	
1.3. Commercial Contact		
1.3.1. Commercial Contact Name	X	
1.3.2. Commercial Contact Phone	X	
1.3.3. Commercial Contact Email	X	
1.3.4. Commercial Contact Address	X	
1.4. Supplier Contact		
1.4.1. Supplier Contact Name	X	
1.4.2. Supplier Contact Phone	X	
1.4.3. Supplier Contact Email	X	
1.4.4. Supplier Contact Address	X	
<b>2. Project Overview</b>		
2.1. Name of business or Industry	X	
2.2. Business or Industry Location	X	
2.3. Proposed In-Service Date	X	
2.4. General Description of Proposed Installation	X	
<b>3. Generator Data</b>		
3.1. Type	X	
3.2. Manufacturer / Model	X	
3.3. Prime Mover Type	X	
3.4. Number of generators	X	
3.5. Generator Nominal Rated kW	X	
3.6. Generator Nominal Rated kVA	X	
3.7. Generator Nominal Rated kV	X	
3.8. Power factor at rated output	X	
3.9. Maximum Authorized Real Power (MARP)		X
3.10. Leading and Lagging Reactive Power at MARP		X
3.11. Generator Grounding		X
3.12. Projected Annual Energy Production (MWh-yr)		X
3.13. Production capacity range (MW)		X
<b>4. Transformer Data (if applicable)</b>		
4.1. Transformer kVA Ratings	X	
4.2. Transformer kV Ratings	X	
4.3. Cooling Type (ONAN, ONAF)	X	



## Technical Interconnection Requirements for Commercial and Institutional Power Producers

### Technical Questionnaire

#### Information required from CIPP – Proposal Stage

INFORMATION REQUIRED FROM IPP		
	REQUIRED AT PROPOSAL STAGE	REQUIRED AT DETAIL DESIGN STAGE
4.4. Winding Connection	X	
4.5. Grounding Impedance (Ohms), if applicable	X	
4.6. Positive Sequence Impedance (% at ONAN base)	X	
4.7. Zero Sequence Impedance (% at ONAN base)	X	
4.8. On-Load Tap Range		X
4.9. On-Load Tap Size		X
4.10. Off-Load Tap Range		X
4.11. Off-Load Tap Range		X
4.12. Factory Test Reports		X
<b>5. Drawings</b>		
5.1. Preliminary Protection and Metering Single Line Diagram	X	
5.2. Complete Protection and Control Diagrams		X
5.3. Complete Single Line Diagram of the Commercial or Institutional Operation including the new generation source		X
5.4. Major Equipment Nameplates (Transformer, Generator, etc.)		X
<b>6. Voltage Regulator (if applicable)</b>		
6.1. Voltage Regulator Range (V)		X
6.2. Accuracy Tolerance (%)		X
<b>7. Compliance with Electrical Inspector</b>		
7.1. Permit or Equivalent Compliance		X
<b>8. Metering Requirements</b>		
8.1. Metering Type (2 Element, 3 Element)		X
8.2. Metering Service Provider		X
8.3. Metering Data Provider		X
8.4. Asset ID Number		X
<b>9. Other information</b>		
9.1.		
9.2.		
9.3.		
9.4.		
9.5.		
9.6.		
9.7.		
9.8.		



ᑭᓄᓴᓴᓴ ᑲᓴᓴᓴᓴᓴᓴᓴᓴ ᑲᓴᓴᓴᓴ  
Quilliq Energy Corporation  
Société d'énergie Quilliq  
Quilliq Aᓴᓴᓴᓴᓴᓴᓴᓴ ᓴᓴᓴᓴᓴᓴᓴᓴ

## Technical Interconnection Requirements and Guidelines for Commercial and Institutional Power Producers

Technical Specification

**Technical Interconnection Requirements**

---

# Appendix B: Information Provided by the Utility



---

After receiving the application for interconnection, QEC shall provide the following information to the CIPP, if available:

1. Single-line diagrams or maps of the Distribution System to the POI (if applicable);
2. Maximum and minimum, normal and emergency system operating voltage ranges at the POI;
3. Harmonic impedance envelope at the POI if available;
4. Planning, operating and reliability criteria, standards and policies;
5. Results of a study (interconnection study) documenting the availability of the requested amount of system capacity;
6. Cost estimates and time schedule to build the upstream facilities;
7. Clearing and reclosing times for single-phase and multiple-phase faults occurring on the Distribution System;
8. Characteristics and settings of protection on the Distribution System;
9. Costs of studies and any required changes to the Distribution System;
10. QEC Distribution Engineering Standards document.

Some or all of this information shall be required by the CIPP to properly design the interconnection protection. QEC shall identify when the costs of producing this information are to be assigned to the CIPP.

---



ᑭᓄᓴᓴᓴ ᑲᓴᓴᓴᓴᓴᓴᓴᓴ ᓴᓴᓴᓴᓴ  
Quilliq Energy Corporation  
Société d'énergie Quilliq  
Quilliq Aᓴᓴᓴᓴᓴᓴᓴᓴ ᓴᓴᓴᓴᓴᓴᓴᓴ

## Technical Interconnection Requirements and Guidelines for Commercial and Institutional Power Producers

Technical Specification

**Technical Interconnection Requirements**

---

# Appendix C: Interconnection Single-Line Diagrams






- 25- SYNCHRONISM CHECK  
27- UNDER VOLTAGE  
47- PHASE SEQUENCE  
50/51- INSTANTANEOUS/TIMED OVERCURRENT  
50N- GROUND OVERCURRENT  
51G- NEUTRAL OVERCURRENT  
51N- NEUTRAL OVERCURRENT WITH DELAY  
59- OVERVOLTAGE  
59G- GROUND OVERVOLTAGE  
67- DIRECTIONAL OVERCURRENT  
81/O- OVER-FREQUENCY  
81/U- UNDER-FREQUENCY


NOTES:


1. TYPICAL REQUIREMENTS SHOWN. GENERATOR OWNER SHALL EVALUATE REQUIREMENTS FOR FURTHER PROTECTION.
2. TYPICAL AUXILIARY CONNECTION SHOWN. OTHER AUXILIARY POWER OPTIONS MAY BE POSSIBLE.

PROFESSIONAL STAMP	PERMIT STAMP	TECHNICAL INTERCONNECTION REQUIREMENT			 ᑭᓄᓐ ᓇᓂᓄᓐ ᓂᓕᓄᓐ ᓇᓂᓄᓐ ᓇᓂᓄᓐ Qulliq Energy Corporation Société d'énergie Qulliq Qulliq Aluyaktutunik Ikumatjutiit
		SINGLE LINE DIAGRAM TYPICAL INTERCONNECTION FOR CIPP DIRECTLY CONNECTED THROUGH QEC'S POWER DISTRIBUTION SYSTEM			
		AUTHORIZED BY XXXX		DRAWN BY J. CABANA BANVILLE	
		DATE: 2020-08-28		STANDARD NO. XXXXXX	
		SCALE NTS	SHEET 1 OF 1	REV -	

## QEC DISTRIBUTION NETWORK

1. AC EXTERNAL (OUTSIDE) UTILITY DISCONNECT, LOCKABLE, VISIBLE BREAK AND READILY ACCESSIBLE.
2. REQUIRE FOR MULTIPLE INVERTERS SYSTEM.



PROFESSIONAL STAMP	PERMIT STAMP	TECHNICAL INTERCONNECTION REQUIREMENT		 ᑭᓴᓴᓴ ᓴᓴᓴᓴᓴᓴᓴᓴ ᓴᓴᓴᓴᓴᓴᓴᓴ Quilliq Energy Corporation Société d'énergie Quilliq Quilliq Aliruyaktugtunik Ikumatjutiit		
		SINGLE LINE DIAGRAM CIPP CONNECTED THROUGH EXISTING MAIN AC PANEL TYPICAL INVERTER-BASED RDG				
		AUTHORIZED BY XXXX	DRAWN BY J. CABANA BANVILLE	SCALE NTS	SHEET 1 OF 1	REV -
		DATE: 2020-08-28	STANDARD NO. XXXXXX			

PROTECTION LEGEND:


AI- ANTI ISLANDING  
25- SYNCHRONISM CHECK  
27- UNDER-VOLTAGE  
50- INSTANTANEOUS OVERCURRENT  
51- TIMED OVERCURRENT  
59- OVERVOLTAGE  
67- DIRECTIONNALL OVERCURRENT  
81/O- OVER-FREQUENCY  
81/U- UNDER-FREQUENCY

NOTES:

1. TYPICAL REQUIREMENTS SHOWN. GENERATOR OWNER SHALL EVALUATE REQUIREMENTS FOR FURTHER PROTECTION.
2. SOME OF THE PROTECTION FUNCTION MAY NOT BE REQUIRED.
3. AC EXTERNAL (OUTSIDE) UTILITY DISCONNECT, LOCKABLE, VISIBLE BREAK AND READILY ACCESSIBLE.

## QEC DISTRIBUTION NETWORK

POINT OF INTERCONNECTION OF  
COMMERCIAL AND INSTITUTIONAL  
FACILITY (POI)

PROFESSIONAL  
STAMPPERMIT  
STAMP

## TECHNICAL INTERCONNECTION REQUIREMENT

SINGLE LINE DIAGRAM  
CIPP CONNECTED THROUGH EXISTING MAIN AC PANEL  
TYPICAL THREE-PHASE RDG

AUTHORIZED BY  
XXXX

DRAWN BY  
J. CABANA BANVILLE

DATE:  
2020-08-28

STANDARD NO.	XXXXXX
--------------	--------



ᑭᓄᓐᓂᓄᓐ ᐅᓕᓕᓄᓐᓂᓐᓂᓐ ᐱᓕᓄᓐ  
Qulliq Energy Corporation  
Société d'énergie Qulliq  
Qulliq Airuyaktugtunik Ikumatjutiit

SCALE NTS	SHEET 1 OF 1	REV -
--------------	-----------------	----------





ᑭᓄᓴᓴᓴ ᓴᓴᓴᓴᓴᓴᓴᓴᓴ ᓴᓴᓴᓴᓴ  
Quilliq Energy Corporation  
Société d'énergie Quilliq  
Quilliq Airuyaktuqtunik Ikumatjutiit

## Technical Interconnection Requirements and Guidelines for Commercial and Institutional Power Producers

### Technical Specification Technical Interconnection Requirements

---

# Appendix D: Application Guidelines



---



## Prospective IPP Application Guideline for Commercial and Institutional Power Producer

### Application Guideline

---

#### **LIMITATION OF LIABILITY AND DISCLAIMER**

Qulliq Energy Corporation (QEC), its officers, directors and employees, make no warranties or representations and take no responsibility of any kind with respect to the information contained in this document, including, without limitation, its quality, accuracy, completeness or fitness for purpose. QEC will not be liable for and accepts no responsibility for any losses, claims, expenses or damages, if any, suffered by a user or because of any decisions made or actions taken or not taken based on this document. Any conclusions a user may derive from the information in this document or any reliance by the user on the information it contains shall be at the user's sole risk. The use of or compliance with these requirements may not absolve an CIPP of liability to QEC for any damages that QEC may be entitled to at law.

QEC reserves the right to amend any of these guidelines at any time without prior notice or warning to users of the information contained herein.

---

## TABLE OF CONTENTS

1. Purpose and limitations .....	1
1.1 Purpose .....	1
1.2 Limitations .....	1
1.3 Liability .....	1
2. Terms, definitions, and abbreviations .....	2
2.1 Definitions .....	2
2.2 Abbreviations .....	3
3. General .....	3
4. Interconnection application stage gates .....	4
4.1 Stage 1 – Exploratory .....	4
4.2 Stage 2 – Preliminary estimates and interconnection study .....	5
4.3 State 3 – Agreement .....	6
4.4 Stage 4 – Construction and commissioning .....	6
5. Adherence to timelines .....	7

## 1. PURPOSE AND LIMITATIONS

### 1.1 Purpose

These application guidelines intended to help Prospective Commercial and Institutional Power Producers (CIPP) understand the process they must undergo in order to apply for the connection of a Renewable Generation Facility to one of QEC's Power Distribution Systems.

The intended use of this document is to:

- a. inform and provide guidelines;
- b. give context of the expectations from the Prospective CIPP and QEC;
- c. define the required documentation and information and a sequence of events for the application process.

The guidelines in this document do not address any liability provisions agreed to elsewhere, such as in the Power Purchase Agreement (PPA) and Generation & Connection Agreement between the Prospective CIPP and QEC.

The application guidelines are also not intended to provide technical requirements for the interconnection of a new Renewable Generation Facility.

### 1.2 Limitations

The application guideline is a minimum requirement for the application process. The Prospective CIPP may also have to meet additional or modified requests to address unique situations as deemed necessary by QEC.

### 1.3 Liability

Neither QEC nor any of their employees or agents shall be or become agents of the CIPP.

QEC's review of the specifications and detailed plans shall not in any way be construed as confirming or endorsing the design or as warranting the safety, durability or reliability of the CIPP's facilities nor shall it be construed to be in lieu of the approvals required from the relevant authorities.

QEC, by reason of such review or lack of review, shall not be responsible for the strength, adequacy of design or capacity of equipment built pursuant to such specifications, nor shall QEC, or any of its employees or agents, be responsible for any injury to the public or workers resulting from the operation of the CIPP Renewable Generation Facilities. This guideline does not absolve the CIPP of the responsibility to maintain and protect its own equipment and QEC's equipment, as well as to ensure the safety of its own personnel, QEC's personnel and the general public.



“**SLD**” or “**Single-Line Diagram**” means a simplified electrical representation of the power system that identifies electrical equipment with related interconnections, which will be attached to the PPA(s).

“**TIR**” or “**Technical Interconnection Requirements**” refers to the TIR document, which establishes criteria, requirements, guidelines and standards that must be met in order to ensure that Renewable Generation Facility interconnections do not adversely affect the safety, power quality or reliability of QEC’s Power Distribution System.

## 2.2 Abbreviations

Abbreviation	Definition
AC	Alternating Current
CIPP	Commercial and Institutional Power Producer
DC	Direct Current
DG	Distributed Generation
PCC	Point of Common Coupling
POI	Point of Interconnection
PPA	Power Purchase Agreement
QEC	Qulliq Energy Corporation
SLD	Single-Line Diagram
TIR	Technical Interconnection Requirements

## 3. GENERAL

It will be the Prospective CIPP’s responsibility to ensure that the Renewable Generation Facility is designed for an interconnection that meets the requirements defined in the CIPP Technical Interconnection Requirements and Guidelines (TIR) document.

It should be noted that some local QEC Power Distribution Systems and/or QEC power plants may require upgrades in order to allow interconnecting a Renewable Generation Facility. Some communities have older installations that were not originally designed to accommodate additional generation sources. It will be the CIPPs’ responsibility to determine the feasibility and upgrade requirements for their projects and all such costs will be borne by the CIPP.

For all interconnections, the Prospective CIPP will go through five stages:

- Stage 1 – Exploratory
- Stage 2 – Preliminary Estimates & Interconnection Study
- Stage 3 – Agreement
- Stage 4 – Construction and Commissioning



- c. The proposed interconnection:
  - i. Technical requirements;
  - ii. Need for Connection Impact Assessment (CIA) Study by QEC
  - iii. Electrical permits and inspection; and
  - iv. GCA and Operating Procedures.
- d. The power purchase process and agreements:
  - i. Terms of payment in PPA;
  - ii. Compensation during pre-commercial testing; and
  - iii. Metering.

QEC will perform a Connection Impact Assessment (CIA), to ensure that the proposed Renewable Generation Facility is safe to operate on the QEC Power Distribution Network without causing adverse effects. To conduct the CIA study, QEC will require, complete technical details of the proposed Renewable Generation Facility and equipment, as per Appendix A. All costs for this assessment will be borne by the Prospective CIPP. After payment is received, QEC will complete the assessment and provide the preliminary estimates of the construction costs to interconnect within 180 calendar days.

As part of the exploratory stage, QEC, in its sole discretion, will determine the suitability and acceptability of the Prospective CIPP's proposed interconnection and grant permission to continue with the proposed installation. The above discussions will also help guide the Prospective CIPP and better approximate the cost that the Prospective CIPP will pay to interconnect.

#### 4.2 Stage 2 – Preliminary estimates and interconnection study

Once it has received permission to move forward from QEC, the Prospective CIPP shall provide a written notice to QEC of its decision to proceed. This decision will then prompt QEC to begin estimating the preliminary interconnection costs (if any) to be incurred by the Prospective CIPP.

The written notice from the Prospective CIPP shall also include the following information:

1. Single-Line Diagram ('SLD') of the commercial or institutional operation with the proposed Renewable Generation Facility;
2. Agreed upon Generator capacity, type (wind, solar, hydro, geothermal, etc.), energy output profile;
3. Agreed upon POI;
4. Energy output profile of the Renewable Generation Facility; and



5. Interconnection study (if applicable).

Once submitted to QEC, any change in the Renewable Generation Facility design will be considered a new interconnection inquiry and may be returned to Stage 1 for further analysis by QEC.

Within 120 calendar days of receiving the written request, QEC shall review the Interconnection Study results and provide preliminary estimates of the construction costs to interconnect the Prospective CIPP Renewable Generation Facility if applicable. Preliminary estimates shall be approximately 25% of the actual construction costs.

The Prospective CIPP shall, within a reasonable time after receipt of all information from QEC as contemplated in this Stage, advise QEC in writing that it intends to proceed to Stage 3 (the "Agreement Stage").

#### 4.3 State 3 – Agreement

QEC may permit the Prospective CIPP to delay proceeding to the Agreement Stage for up to 60 days following receipt by the Prospective CIPP of the Interconnection Study and cost estimates for the interconnection, provided that the delay does not materially affect the interconnection request. If QEC determines, in its sole discretion, that the interconnection request is materially affected by the delay, the interconnection request shall be rejected. If the Prospective CIPP subsequently wishes to proceed with the interconnection, it must return to Stage 1 of these interconnection procedures.

Within 90 days of the written notification by the Prospective CIPP that it intends to proceed, QEC will forward the PPA and GCA to the prospective CIPP.

The details to be found in the PPA and GCA shall include, among other things, the construction responsibilities of the Prospective CIPP, obligations related to operating and maintaining the Renewable Generation facilities, insurance requirements, creditworthiness requirements and delineates the rights of the parties on termination of the interconnection.

#### 4.4 Stage 4 – Construction and commissioning

It shall be the responsibility of the Prospective CIPP to undertake and complete all activities related to the construction and commissioning of the Renewable Generation Facility while complying with the applicable codes and standards and ensuring compatibility between the Renewable Generation Facility and QEC systems. The Prospective CIPP shall, at least two weeks prior to final inspection of its facility, notify QEC that such inspection will be taking place. QEC shall have the right to have a representative present at the final inspection.

Immediately prior to commissioning and every five years thereafter, performance data (as defined in the TIR) of the Renewable Generation Facility shall be provided to QEC by the Prospective CIPP, which will be verified against the Interconnection Study.

## 5. ADHERENCE TO TIMELINES

If QEC is unable to complete the required Interconnection Study or Agreements within a reasonable time, QEC shall notify the Prospective CIPP and provide an estimated completion date along with an explanation as to why additional time is required.

The Prospective CIPP may also request reasonable extensions of any deadline set forth in these interconnection procedures. A reasonable extension shall be granted if in the judgment of QEC the extension does not cause any additional burden/costs to QEC. Any request for an extension shall be made in writing by the Prospective CIPP to the QEC representative.



ᑭᓄᓴᓴᓴ ᓴᓴᓴᓴᓴᓴᓴᓴᓴ ᓴᓴᓴᓴ  
Quilliq Energy Corporation  
Société d'énergie Quilliq  
Quilliq Aᓴᓴᓴᓴᓴᓴᓴᓴᓴ ᓴᓴᓴᓴᓴᓴᓴᓴᓴ

## Technical Interconnection Requirements and Guidelines for Commercial and Institutional Power Producers

Technical Specification  
**Technical Interconnection Requirements**

---

# Appendix E: Operating Procedures





## Operating Agreement for Commercial and Institutional Power Producers

### Operating Procedures

---

#### **LIMITATION OF LIABILITY AND DISCLAIMER**

Qulliq Energy Corporation (QEC), its officers, directors and employees, make no warranties or representations and take no responsibility of any kind with respect to the information contained in this document, including, without limitation, its quality, accuracy, completeness or fitness for purpose. QEC will not be liable for and accepts no responsibility for any losses, claims, expenses or damages, if any, suffered by a user or because of any decisions made or actions taken or not taken based on this document. Any conclusions a user may derive from the information in this document or any reliance by the user on the information it contains shall be at the user's sole risk. The use of or compliance with these requirements may not absolve an CIPP of liability to QEC for any damages that QEC may be entitled to at law.

QEC reserves the right to amend any of these guidelines at any time without prior notice or warning to users of the information contained herein.

---

## TABLE OF CONTENTS

1. Purpose and limitations .....	1
1.1 Purpose .....	1
1.2 Liability .....	1
2. Terms, definitions, and abbreviations .....	1
2.1 Definitions .....	1
2.2 Abbreviations .....	2
3. Operational information .....	2
3.1 Contact information .....	2
3.2 Circuit breaker identification .....	2
3.3 Interlocks .....	2
3.4 Normal operation .....	3
4. Operating procedures .....	3
4.1 Line isolation .....	3
4.2 Voltage support .....	3
4.3 Remote monitoring and control .....	4
5. Operational notifications .....	4
5.1 Daily operating communications .....	4
5.2 IPP facility planned maintenance and scheduling .....	4
5.3 Distribution maintenance and scheduling .....	4

## 1. PURPOSE AND LIMITATIONS

## 1.1 Purpose

This document outlines the steps to be taken or procedures to be followed to ensure a reliable and safe operation and interconnection between the CIPP's Renewable Generation Facility and QEC's Power Distribution System through a variety of circumstances.

## 1.2 Liability

Under no circumstances shall QEC be liable for the actions of the CIPP, the CIPP's employees or agents.

## 2. TERMS, DEFINITIONS, AND ABBREVIATIONS

## 2.1 Definitions

**“CIPP” or “Commercial and Institutional Power Producer”** means a Commercial or Institutional customer who has signed a PPA with QEC to design, construct, develop, install, own, operate and maintain a Renewable Generation Facility.

**“Operating Authority”** means the organizational unit, which is assigned the responsibility for the operation of a portion of the electrical system.

“**POI**” or “**Point of Interconnection**” means the point at which QEC's facilities are connected to the CIPP's facilities or conductors, and where any transfer of electric energy between the CIPP and QEC takes place. POI is commonly referred to as the Point of Common Coupling (PCC) in multiple standards.

**“Power Distribution System”** means the distribution, protection, control and communication facilities in Nunavut that are or may be used in connection with, or that otherwise relate to, the distribution of electrical energy at 25 kilovolts or less, and includes all additions and modifications thereto and repairs or replacements thereof.

“**QEC**” means Qulliq Energy Corporation, the utility that owns the Power Distribution System that a CIPP intends to interconnect with and will buy power produced by the Renewable Generation Facility.

**“Renewable Generation Facility”** means any independent renewable electric generator of the CIPP connected to QEC’s Power Distribution System through the Point of Interconnection.

## 2.2 Abbreviations

Abbreviation	Definition
AC	Alternating Current
CIPP	Commercial and Institutional Power Producer
DC	Direct Current
DG	Distributed Generation
PCC	Point of Common Coupling
POI	Point of Interconnection
PPA	Power Purchase Agreement
QEC	Qulliq Energy Corporation
SLD	Single-Line Diagram
TIR	Technical Interconnection Requirements

## 3. OPERATIONAL INFORMATION

### 3.1 Contact information

<QEC Community Name> Power Plant – Phone (867) XXX-XXXX

Contact Name	Title	Phone Number
		(867) XXX-XXXX
		(867) XXX-XXXX
		(867) XXX-XXXX
		(867) XXX-XXXX
		(867) XXX-XXXX

### 3.2 Circuit breaker identification

List circuit breakers providing interconnection between the CIPP and the utility.

### 3.3 Interlocks

List identified circuit breaker interlocks with sequence information.

### 3.4 Normal operation

Under normal operating conditions, the CIPP facility will be connected to the utility grid. The breaker status under normal operating conditions is as follows:

Breaker	Status
<Breaker ID>	Open / Closed
<Breaker ID>	Open / Closed
<Breaker ID>	Open / Closed
<Breaker ID>	Open / Closed
<Breaker ID>	Open / Closed

## 4. OPERATING PROCEDURES

### 4.1 Line isolation

Isolation of line <XXX> requires the minimum notification defined in Section 4.3, with the exception of emergency repairs.

QEC will provide a Condition Guarantee, which shall be used in all communications between external parties for breaker <Breaker ID>. It is a formal method of communication to ensure that switching has been completed and that the status of the breaker will not change until the work is completed, the lock out/tag out is surrendered and all workers are clear.

### 4.2 Voltage support

Based on the power quality conditions defined in the TIR document and system security requirements, QEC may request voltage support. Voltage support can be provided by placing the CIPP generation source on line, or by other means such as capacitor banks or transformer tap changing. If such support is part of the operating procedure then:

1. When the CIPP has a generation source on line, the generators regulate the generator bus voltage ranging from 100% to 105% of the nominal voltage, and QEC shall have control of this setpoint. The generators reactive output will be adjusted by the utility in real time, to regulate the system voltage, by pulsing the AVR voltage setpoints. The CIPP sets the acceptable range within which the utility can adjust voltage.
2. QEC shall have full SCADA visibility of the CIPP substation and control of critical elements.



#### 4.3 Remote monitoring

All CIPP requests shall be communicated and approved by QEC.

QEC shall have monitoring of the incoming line breaker <Breaker ID> at the CIPP facility and have visual indication of the CIPP breakers, generator status, capacitor status and electrical measurement information for the CIPP facility.

QEC control shall be limited to:

1. Approving requests from the CIPP to connect and disconnect from the utility system;
2. Approving requests from the CIPP for changes in the generation output;
3. Requesting the CIPP to disconnect from the utility system for operational, reliability and safety reasons.

### 5. OPERATIONAL NOTIFICATIONS

#### 5.1 Daily operating communications

Under normal operating conditions, the CIPP will be supplying <XXX> kW to the QEC Power Distribution System. Generation changes of more than <XXX> kW must be communicated and approved by QEC.

The transition from winter to summer and conversely summer to winter generation levels must be established with QEC with a minimum of 30-days' notice.

#### 5.2 CIPP facility planned maintenance and scheduling

The CIPP shall operate under QEC's approved maintenance procedures.

To meet changing operating conditions and coordinate maintenance efforts, maintenance shutdowns by the CIPP need to be communicated to QEC at least 24 hours in advance. Changes in the availability and capacity of the onsite generation sources shall be communicated to QEC.

#### 5.3 Distribution maintenance and scheduling

QEC performs annual line maintenance on its distribution lines; during this maintenance, the grid power to the CIPP facility may be disrupted or suspended. QEC shall provide a minimum of 24 hours notice before the intended start date as well as provide the expected duration of the work that will curtail or otherwise interrupt the supply of grid power to the CIPP facility.



ᑭᓄᓴᓴᓴ ᓴᓴᓴᓴᓴᓴᓴᓴᓴ ᓴᓴᓴᓴ  
Quilliq Energy Corporation  
Société d'énergie Quilliq  
Quilliq Airuyaktuqtunik Ikumatjutiit

## Technical Interconnection Requirements and Guidelines for Commercial and Institutional Power Producers

### Technical Specification Technical Interconnection Requirements

---

# Appendix F: QEC Power Plant General Information



---



## Prospective IPP Application Guideline for Independent Power Producer

### QEC Power Plant Data

---

#### **LIMITATION OF LIABILITY AND DISCLAIMER**

Qulliq Energy Corporation (QEC), its officers, directors and employees, make no warranties or representations and take no responsibility of any kind with respect to the information contained in this document, including, without limitation, its quality, accuracy, completeness or fitness for purpose. QEC will not be liable for and accepts no responsibility for any losses, claims, expenses or damages, if any, suffered by a user or because of any decisions made or actions taken or not taken based on this document. Any conclusions a user may derive from the information in this document or any reliance by the user on the information it contains shall be at the user's sole risk. The use of or compliance with these requirements may not absolve an CIPP of liability to QEC for any damages that QEC may be entitled to at law.

QEC reserves the right to amend any of these guidelines at any time without prior notice or warning to users of the information contained herein.

---

## TABLE OF CONTENTS

1. Background.....	1
1.1 Introduction.....	1
1.2 Plant Description - Baffin Region .....	1
1.2.1 Iqaluit - 701 .....	1
1.2.2 Pangnirtung – 702 .....	2
1.2.3 Kinngait Power Plant – 703 .....	2
1.2.4 Resolute Bay power plant – 704 .....	2
1.2.5 Pond Inlet power plant – 705.....	3
1.2.6 Igloolik power plant – 706.....	3
1.2.7 Sanirajak power plant – 707 .....	3
1.2.8 Qikiqtarjuaq power plant – 708.....	4
1.2.9 Kimmirut power plant – 709.....	4
1.2.10 Arctic Bay power plant – 710.....	4
1.2.11 Clyde River power plant – 711 .....	5
1.2.12 Grise Fiord power plant – 712 .....	5
1.2.13 Sanikiluaq power plant – 713 .....	5
1.3 Plant Description - Kivalliq Region .....	6
1.3.1 Rankin Inlet power plant – 601 .....	6
1.3.2 Baker Lake power plant – 602.....	6
1.3.3 Arviat power plant – 603.....	6
1.3.4 Coral Harbour Power plant – 604.....	7
1.3.5 Chesterfield Inlet power plant – 605.....	7
1.3.6 Whale Cove power plant – 606 .....	7
1.3.7 Nauyasat power plant – 607 .....	8
1.4 Plant Description - Kitikmeot Region.....	8
1.4.1 Cambridge Bay power plant – 501 .....	8
1.4.2 Gjoa Haven power plant – 502.....	8
1.4.3 Taloyoak power plant – 503 .....	9
1.4.4 Kugaaruk power plant – 504 .....	9
1.4.5 Kugluktuk power plant – 505 .....	9

## 1. BACKGROUND

## 1.1 Introduction

The Qulliq Energy Corporation (QEC) owns and operates 25 standalone diesel power generating stations throughout Nunavut. These power generating stations have engine/generator sets (“Genset”) ranging in various capacities as mentioned below as per community energy requirement and load growth projected. Genset ratings for Grise Fiord and Kinngait plants are for new plants that were commissioned in Dec 2018.

## 1.2 Plant Description - Baffin Region

### 1.2.1 Iqaluit power plant- 701

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	3,000 (Wartsila 9R32) Sr No 5880	720	9,707 kW 59,646 MWh (2017)  10,946 kW 65,901 MWh (2025)  Average generation 2017 - 4,901,305 kWh	63°44'55" N 68°31'11" W
G2	2,500 (EMD20V645) Sr No 75C1042	900		
G3	3,300 (CAT D3612) Sr No 9RC114	720		
G4	2,000 (Wartsila 12V200) Sr No 120071	1,200		
G5	4,300 (Wartsila 12V32) Sr No 5337	720		
G6	5,000 (Wartsila 12V32) Sr No 227817	720		
G7	5,000 (Wartsila 12V32) Sr No 227818	720		
G8	330 (Series 60 Detroit Diesel) Sr No 06R0874156	1,800		
G9 - EM	320 (D 3406 CAT) Sr No 1LS01153	1,200		
Total	25,430			

## 1.2.2 Pangnirtung power plant – 702

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	1,100 (Cummins DQGAF) QSK-50-G5 Sr No 25415690	1,800	1,208 kW 6,418 MWH (2017)  1,302 kW 6,720 MWH (2025)	66°08'52" N 65°41'58" W
G2	1,100 (Cummins DQGAF) QSK-50-G5 Sr No 25415035	1,800		
G3	680 (Cummins DQGAA) QST-30-G5 Sr No 37268145	1,800		
G4 - EM	550 (C27 Caterpillar MJE03777 Sr No C27HGDGS00402	1,800		
<b>Total</b>	<b>2,880</b>			

## 1.2.3 Kinngait power plant – 703

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	1,100 (16V4000G73 MTU)	1,200	1,488 kW 5,509 MWH (2017)  1,600 kW 6,087 MWH (2025)	64°13'54" N 76°32'25" W
G2	1,100 (16V4000G73 MTU)	1,200		
G3	525 (8V4000M63 MTU)	1,200		
G4	830 (12V4000G73 MTU)	1,200		
<b>Total</b>	<b>3,555</b>			

## 1.2.4 Resolute Bay power plant – 704

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	320 (Series 60 Detroit Diesel) Sr No 06R1025516	1,800	829 kW 4,580 MWH (2017)  810 kW 4,419 MWH (2025)	74°41'51" N 94°49'56" W
G2	350 (F2895 Waukesha) F2895 Sr No 230803	1,200		
G3	500 (8V400 Detroit Diesel) 8V4000 Sr No 524101744	1,200		
G4	320 (CAT D3406E) Sr No 17300670	1,200		
G5	320 (CAT D3406E) Sr No 9NN00445	1,200		
<b>Total</b>	<b>1,810</b>			

### 1.2.5 Pond Inlet power plant – 705

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
<b>G1</b>	720 (CAT D 3512) Sr No 67Z00917	1,200	1,168 kW 6,402 MWH (2017)  1,356 kW 7,170 MWH (2025)	72°41'57" N 77°57'33" W
<b>G2</b>	850 (Detroit 12V4000) Sr No 5262011374	1,200		
<b>G3</b>	550 (Gauscor F360TA) Sr No 76937	1,200		
<b>G4</b>	550 (Gauscor SF360TA) Sr No 76936	1,200		
<b>Total</b>	<b>2,670</b>			

### 1.2.6 Igloolik power plant – 706

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
<b>G1</b>	850 (Detroit Diesel 12V4000) Sr No 5262011373	1,200	1,247 kW 6,771 MWH (2017)  1,471 kW 7,759 MWH (2025)	69°22'34" N 81°47'58" W
<b>G2</b>	480 (CAT D 3508) Sr No 70Z00838	1,200		
<b>G3</b>	720 (CAT D 3512) Sr No 67Z01250	1,200		
<b>G4 - EM</b>	320 (Series 60 Detroit Diesel) 06R0842989	1,800		
<b>Total</b>	<b>2,050</b>			

### 1.2.7 Sanirajak power plant – 707

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
<b>G1</b>	165 (CAT D3406) 90U15752	1,200	681 KW 3374 MWH (2017)  764 KW 3831 MWH (2025)	68°46'38" N 81°13'27" W
<b>G2</b>	550 (D3508B) Sr No CTC00294	1,200		
<b>G3</b>	330 (Series 60 Detroit Diesel) 06R1010847	1,800		
<b>G4</b>	550(CAT 3508B) Sr No 2HW00394	1,200		
<b>Total</b>	<b>1,525</b>			

### 1.2.8 Qikiqtarjuaq power plant – 708

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
<b>G1</b>	300 (MTU8V1600B3OS) Sr No 1HTMMAA2AH261600	1,800	1,100 kW 2,765 MWH (2017)  1,195 KW 3,029 MWH (2025)	67°33'29" N 64°01'29" W
<b>G2</b>	550 (CAT D3508B) Sr No S2A00177	1,200		
<b>G3</b>	550 (CAT D3508B) Sr No S2A00178	1,200		
<b>G4</b>	370 (CAT C15) Sr No FTH04668	1,800		
<b>Total</b>	<b>1,770</b>			

### 1.2.9 Kimmirut power plant – 709

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
<b>G1</b>	360 (Volvo TAD 1344GE) Sr No 201333041	1,800	385 kW 2,004 MWH (2017)  389 kW 1,985 MWH (2025)	62°50'48" N 69°52'07" W
<b>G2</b>	300 (Series 60 Detroit Diesel) Sr No 06R0793390	1,800		
<b>G3</b>	330 (CAT D 3412) Sr No 81Z11897	1,200		
<b>G4</b>	350 EM (CAT D3406) 1DZ03760	1,200		
<b>Total</b>	<b>990</b>			

### 1.2.10 Arctic Bay power plant – 710

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
<b>G1</b>	480 (CAT D3508) Sr No 70Z00908	1,200	690 KW 3,361 MWH (2017)  759 KW 3,661 MWH (2025)	73°02'11" N 85°09'09" W
<b>G2</b>	290 (CAT D 3406) Sr No 9FF01874	1,200		
<b>G3</b>	330 (Series 60 Detroit Diesel) Sr No 06R0976524	1,800		
<b>G4 - EM</b>	320 (Series 60 Detroit Diesel) Sr No 06R0984997	1,800		
<b>Total</b>	<b>1,100</b>			



### 1.2.11 Clyde River power plant – 711

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	480 (CAT 3508B) Sr No 70Z00857	1,200	796 kW 3,792 MWH (2017)  886 kW 4,319 MWH (2025)	70°28'26" N 68°35'10" W
G2	550 (CAT D 3508B) Sr No 2HW00389	1,200		
G3	330 (Series 60 Detroit Diesel) Sr No 06R1043819	1,800		
G4 - EM	550 (CAT D 3508B) Sr No 2HW00390	1,800		
<b>Total</b>	<b>1,910</b>			

### 1.2.12 Grise Fiord power plant – 712

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	255 TAD1344GE-W DC255D6CSW	1,800	168 kW 1,251 MWH (2017)  173 KW 1,067 MWH (2025)	76°25'03" N 82°53'38" W
G2	255 TAD1344GE-W DC255D6CSW	1,800		
G3	225 TAD1344GE-W DC255D6CSW	1,800		
G4	170 TAD1350GE-HCI434DIH	1,800		
<b>Total</b>	<b>905</b>			

### 1.2.13 Sanikiluaq power plant – 713

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	330 (Series 60 Detroit Diesel) Sr No 06R1043819	1,800	725 kW 3,837 MWH (2017)  804 kW 4,112 MWH (2025)	56°32'34" N 79°13'30" W
G2	550 (CAT D 3508B) Sr No 2HW00388	1,200		
G3	550 (CAT 3508B) Sr No CTC00281	1,200		
<b>Total</b>	<b>1,430</b>			

## 1.3 Plant Description - Kivalliq Region

### 1.3.1 Rankin Inlet power plant – 601

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
<b>G1</b>	950 (CAT D3516) Sr No 73Z00621	1,200	3,348 kW 18,490 MWH (2017)  3,344 kW 18,749 MWH (2025)	62°48'35" N 92°05'58" W
<b>G2</b>	1500 (CAT D3606) Sr No 8RB01008	900		
<b>G3</b>	1450 (EMD 8V710) Sr No 06-E1 - 1030	900		
<b>G4</b>	2150 (EMD L12V710) Sr No 01-L1 - 10130	900		
<b>G5 - EM</b>	820EM (Detroit 12V4000) Sr No 5262003102	1,200		
<b>Total</b>	<b>6,870</b>			

### 1.3.2 Baker Lake power plant – 602

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
<b>G1</b>	1100 (Cat D 3516B) Sr No GZT00177	1,200	1,100 kW 8,906 MWH (2017)  2,055 kW 9,224 MWH (2025)	64°19'05" N 96°01'03" W
<b>G2</b>	850 (Cat D 3512B) Sr No CTB00184	1,200		
<b>G3</b>	1050 (Cat D 3516B) Sr No CTA00152	1,200		
<b>G4</b>	550 (Cat D 3508B) Sr No CTC00295	1,200		
<b>Total</b>	<b>3,550</b>			

### 1.3.3 Arviat power plant – 603

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
<b>G1</b>	850 (CAT D 3512B) Sr No LE600186	1,200	1613 kW 8,661 MWH (2017)  1988 kW 10,348 MWH (2025)	61°06'29" N 94°03'25" W
<b>G2</b>	550 (CAT D 3508B) Sr No CTC0292	1,200		
<b>G3</b>	1100 (CAT D 3516B) Sr No GZT00178	1,200		
<b>G4</b>	800 (CAT D 3512B) Sr No 9GZ00571	1,200		
<b>Total</b>	<b>3,300</b>			

### 1.3.4 Coral Harbour power plant – 604

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	480 (CAT D 3508) Sr No 70Z00877	1,200	731 kW 3,541 MWH (2017)  780 kW 3,915 MWH (2025)	64°08'13" N 83°09'51" W
G2	420 (CAT D 3508) Sr No CTF00265	1,200		
G3	420 (CAT D 3508) Sr No CTF00264	1,200		
<b>Total</b>	<b>1,320</b>			

### 1.3.5 Chesterfield Inlet power plant – 605

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	320 (Detroit Series 60) Sr No 06R0793235	1,800	400 kW 2,066 MWH (2017)  412 kW 2,169 MWH (2025)	63°20'27" N 90°42'22" W
G2	320 (Detroit Series 60) Sr No 06R01043820	1,800		
G3	400 (CAT D 379) Sr No 34Z00683	1,200		
<b>Total</b>	<b>1,040</b>			

### 1.3.6 Whale Cove power plant– 606

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	300 (CAT D 3412) Sr No 81Z11643	1,200	380 kW 1,931 MWH (2017)  441 kW 2,153 MWH (2025)	62°10'22" N 92°34'46" W
G2	300 (CAT D 3412) Sr No 81Z11653	1,200		
G3	150 (CAT D3406) Sr No 2WB10298	1,200		
G4	320 (Detroit Series 60) Sr No 06R1043818	1,800		
<b>Total</b>	<b>1,070</b>			

### 1.3.7 Naujaat power plant – 607

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	550 (CAT D 3508B) Sr No CTC00282	1,200	871 kW 4,315 MWH (2017)  1,014 kW 5,014 MWH (2025)	66°31'19" N 86°14'06" W
G2	550 (CAT 3508B) Sr No 2HW00391	1,200		
G3	550 (CAT D 3508B) Sr No CTC00280	1,200		
G4 - EM	550 kW Modular unit (CAT 3508B) Sr No 2HW00393	1,200		
Total	1,650			

## 1.4 Plant Description – Kitikmeot Region

### 1.4.1 Cambridge Bay power plant– 501

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	1100 (Detroit 16V4000) Sr No 5272003461	1,200	2,265 kW 12,902 MWH (2017)  2,453 kW 13,803 MWH (2025)  Average generation 2017 1,010,792 kWh	69°07'02" N 105°03'11" W
G2	550 (CAT D 3508B) Sr No CTC00266	1,200		
G3	1100 (CAT D 3512B) Sr No GZT00174	1,200		
G4	1100 (Detroit 16V4000) Sr No 5272003468	1,200		
G5	1100 (Detroit 16V4000) Sr No 5272001410	1,200		
Total	4,950			

### 1.4.2 Gjoa Haven power plant – 502

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	720 (CAT D3512) Sr No 67Z-00764	1,200	1,100 kW 5,851 MWH (2017)  1,195 kW 6,642 MWH (2025)	68°37'33" N 95°52'30" W
G2	500 (MTU8V4000M63) Sr No 524101864	1,200		
G3	550 (Gauscor SF360TA) Sr No 76934	1,200		
G4	550 (CAT 3508B)	1,200		
Total	2,320			

### 1.4.3 Taloyoak power plant – 5031

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	370 (CAT C15) Sr No FTH04674	1,800	730 kW 3,923 MWH (2017)  851 kW 4,478 MWH (2025)	69°32'13" N 93°31'36" W
G2	550 (CAT 3508B) Sr No S2A00179	1,200		
G3	550 (CAT 3508B) Sr No S2A00180	1,200		
G4	370 (CAT C15) Sr No FTH04673	1,800		
<b>Total</b>	<b>1,840</b>			

### 1.4.4 Kugaaruk power plant – 504

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	320 (Detroit Series 60) Sr No 6R0753348	1,800	669 kW 2,829 MWH (2017)  796 kW 3,330 MWH (2025)	68°31'59" N 89°49'36" W
G2	550 (CAT D 3508B) Sr No CTC00284	1,200		
G3	550 (CAT D 3508B) Sr No CTC00283	1,200		
<b>Total</b>	<b>1,420</b>			

### 1.4.5 Kugluktuk power plant – 505

Genset	Rating (kW) and Make	RPM	Peak Load & Generation 2017 & Forecast 2025	Geographic Location
G1	875 (Detroit DD4000) Sr No 5262000511	1,800	1,077 KW 5,796 MWH (2017)  1,155 KW 6,318 MWH (2025)	67°49'32" N 115°05'42" W
G2	320 (Detroit Series 60) Sr No 6R0649412	1,800		
G3	320 (Detroit Series 60) Sr No 6R0812721	1,800		
G4	720 (CAT D 3512) Sr No 67Z-00939	1,200		
<b>Total</b>	<b>2,235</b>			

**NOTE:** This is a live document, as equipment configuration will change with time as per community needs and life cycle of the equipment. New plants may be built with different equipment configuration and location at the same community. All above information provided by QEC is to be verified by the proponent for admissibility, accuracy and updated as required at the time of use. Load and capacity projections also need to be further extrapolated and extended for the projected life of the new power plant based on the trend and data to be collected by the Proponent. QEC does not guarantee the accuracy of the information provided.



ᑭᓄᓴᓴᓴ ᓴᓴᓴᓴᓴᓴᓴᓴᓴ ᓴᓴᓴᓴ  
Quilliq Energy Corporation  
Société d'énergie Quilliq  
Quilliq Aᓴᓴᓴᓴᓴᓴᓴᓴ ᓴᓴᓴᓴᓴᓴᓴᓴ

## Technical Interconnection Requirements and Guidelines for Commercial and Institutional Power Producers

### Technical Specification Technical Interconnection Requirements

---

# Appendix G: QEC Distribution Systems Voltages



---

